KOLAR DIVISION.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 15th April 1916 for constructing an in-patient ward in the compound of the Local Fund Dispensary at Chikballapur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by end of December 1916,

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, stating the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing an in-patient ward in the compound of Local Fund Dispensary at Chikballapur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circular, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work	Per	Quantity
IN-PATIENT WARD.		
Earthwork excavation and filling basement	Cyd.	160
Concrete in chunam	C. ft.	1067
Burnt stone in chunam	"	3182
Burnt brick in mortar	"	3326
Burnt stone slabs, dressed, 6" thick	S. ft.	722
Pointing with chunam	Sqr.	3·00
Plastering with chunam	"	51·60
White and colourwashing	"	51·60
Flooring with Cadappah slabs over 3" concrete	"	7·27
Flooring with 1st class Mangalore tiles 9" square over 3" concrete and cement pointing	"	3·75
Roofing with 1st class Mangalore tiles over teak rafters, etc., complete	"	23·70
Ridge and Hip tiles set in mortar and cement pointing	Rft.	107
Ventilating tiles	Each	8
Teakwood work, wrought and put up	C. ft.	171·25
Teakwood panelled door with hinges, etc.	S. ft.	208
Teakwood shelves with cross planks, etc.	"	63
Teakwood windows with glazed shutters with iron bars, etc., complete	"	63
Teakwood glazed ventilators	"	111
Teakwood ornamental cave board	Rft.	310
Ornamental large boards including finials	Each	3
Zinc sheets for valleys	S. ft.	75
Teakwood planking ½" valley	S. ft.	75
Teakwood sun shades	Each	8
Cut stone pillars with base and capitals	"	11
Ceiling with Mangalore tiles	Sqr.	7·80
Silicate painting	"	13·50
Clearing site	Lump sum	...
KITCHEN.		
Dismantling compound wall	Lump sum	...
Earthwork excavation and filling basement	Cyd.	29
Concrete in chunam	C. ft.	205
Burnt stone in chunam	"	614
Burnt brick in clay superstructure	"	744
Do in chunam	"	287
Burnt stone slabs dressed	"	87
Chunam plastering	S. ft.	14·36
White and colourwashing	Sqr.	14·36
Pointing with chunam	"	1·30
Teakwood wrought and put up with wood oiling	"	34·50
Roofing with 1st class Mangalore tiles over teak reepers	"	6·46
Ridge tiles set in mortar and cement pointing	Sqr.	32
Teakwood door battened with bolts, etc., complete	R. ft.	50
Do windows with iron bars, etc., complete	S. ft.	45
Flooring with Cudappah slabs over 3" concrete and cement pointing	"	2·64
Silicate painting	"	2·91
Constructing a hearth and iron chimney, etc., complete, lump sum	...	...
Clearing site, etc., complete	...	...
Eave board teakwood plain	R. ft.	82

V. AIYASWAMI IYER,
Executive Engineer, Kolar Division.